

Knauf WARM WALL Natur T in Timber Construction ETICS systems with wood fibre insulation panels

WE203Ta.de – With mineral-based render system

WE203Tc.de – With mineral-based / organic-based render system

Note on English translation / Hinweise zur englischen Fassung

This is a translation of the System Data Sheet valid in Germany.

All stated details and properties are in compliance with the regulations of the German standards and building regulations. They are only applicable for the specified products, system components, application rules, and construction details in connection with the specifications of the respective certificates and approvals.

Knauf Gips KG denies any liability for applications outside of Germany as this requires changes acc. to the respective national standards and building regulations.

Dies ist eine Übersetzung des in Deutschland gültigen Detailblattes. Alle angegebenen Werte und Eigenschaften entsprechen den in Deutschland gültigen Normen und bauaufsichtlichen Regelungen. Sie gelten nur bei Verwendung der angegebenen Produkte, Systemkomponenten, Anwendungsregeln und Konstruktionsdetails in Verbindung mit den Vorgaben der bauaufsichtlichen Nachweise.

Die Knauf Gips KG lehnt jegliche Haftung für Einsatz und Anwendung außerhalb Deutschlands ab, da in diesem Fall eine Anpassung an nationale Normen und bauaufsichtliche Regelungen notwendig ist.

Contents

	Usage instructions	
	Notes I Proofs	3
	Introduction	
	System overview	4
	Data for planning	
	System components	8
	Thermal insulation	12
	Fire resistance	13
	Attachment of the insulation materials	14
	Construction details	
	Plinth application	17
	French door connections	21
	Window connections	23
	Connections to roof	28
	Expansion and connection joints	30
	Connection to building corner I Junction between stories	31
	Vertical extension	32
	Installation and application	
	Preconditions I Machine technology	33
	Insulation materials	34
	Driving-rain proof window connection profiles	39
	Plaster system	41
	Utilization	
	Maintenance	45
	Material requirement	
	Knauf WARM WALL Natur T in Timber Construction	46
	Information on sustainability	
	Knauf WARM WALL Natur T in Timber Construction	48

Notes on the document

Knauf system data sheets are the planning and application basis for the planners and professional installers with the application of Knauf systems. The contained information and specifications, constructions, details and stated products are based, unless otherwise stated, on the Certificates of Usability (e.g. general national technical approvals abZ and general type approvals aBG) valid at the date they are published as well as on the applicable standards. In addition, design and structural requirements and those regarding building physics (fire protection and sound insulation) are considered.

The details shown are solution suggestions intended for general orientation in the subject matter and must be adapted accordingly to suit the constructional features on site. Ancillary trades are only represented schematically.

References to other documents

System data sheets

- ETICS systems with wood fibre insulation panels ISOLAIR and PAVAWALL Knauf WARM WALL Natur D WE203D.de
- ETICS systems with wood fibre insulation panels WF protect / WF protect dry / WF duo dry Knauf WARM WALL Natur S WE203S.de
- Knauf Structural Wood Frame Panels W55.de

Product data sheets

- Observe the product data sheets of the Knauf system components.

Intended use of Knauf Systems

Please observe the following:

Caution

Knauf systems may only be used for the application cases specified in the Knauf documentation. In case third-party products or components are used, they must be recommended or approved by Knauf. Flawless application of products / systems assumes proper transport, storage, assembly, installation and maintenance.

General notes on Knauf systems

Building physics requirements must be examined and tested in detail.

For design of timber structures see EN 1995-1-1 in conjunction with EN 1995-1-1/NA.

To avoid thermal bridges, see DIN 4108 amendment 2.

Freedom from condensation: The assessment of the freedom from condensation (hygrothermal performance) shall be performed in accordance with DIN 4108-3 or EN 15026. A vapour retarder is required on the interior in accordance with the building physics ratings.

The assessment of the thermal insulation shall be performed in accordance with DIN 4108-2 and if required GEG (German energy saving ordinance).

The structural stability of the existing wall must be assured before installation of ETICS. The proof must include all load-bearing and associated elements.

It is essential to ensure that the construction is airtight. Refer to DIN 4108-7 as well as the guideline "Ausführung luftdichter Konstruktionen und Anschlüsse - *Implementing airtight constructions and connections* (German only)" issued by the Fachverband der Stuckateure für Ausbau und Fassade Baden-Württemberg, Germany.

Connections must be carefully planned and must be made driving-rain proof.

Before the application of a plastering system we recommend use of a handover certificate for the transfer of the site to another trade.

Term definition

Splash water zone

The splash water zone starts with the edge of the ground line or top edge of the covering and has a height of at least 300 mm. The use of moisture resistant insulation panels is recommended in this area. Water from precipitation must be diverted away from the façade by constructional measures (gravel bed or layer that interrupts capillary action). Paving stone or paving must be installed sloping away from the building and be constructionally separated from the building. Observe the DIN 18533 as well as the DIN 68800-2.

Explanation of terms

In this system data sheet, the following general type approval / terms that diverge from the system are used:

- Finish coat with paint coat instead of a final coating

Abbreviations used in the document:

- DIBt: Deutsches Institut für Bautechnik - German Institute for Civil Engineering
- EPS: Expanded polystyrene
- GEG: German energy saving ordinance
- VDPM: Verband für Dämmsysteme, Putz und Mörtel e. V. - Federation for Insulation Systems, Plaster and Mortar
- ETICS: External Thermal Insulation Composite System

Notes on fire resistance

In this system data sheet, unless explicitly stated, fire protection concerns are not taken into account in the detailed features shown.

For wall constructions with WARM WALL Natur T and sound insulation see system data sheet Knauf Structural Wood Frame Panels W55.de

Notes on sound insulation

For wall constructions with WARM WALL Natur T and sound insulation see system data sheet Knauf Structural Wood Frame Panels W55.de.

Certificate of Usability

Knauf System	Proof
Knauf WARM WALL Natur T in Timber Construction	Z-33.47-673

The stated constructional and structural properties, and characteristic building physics of Knauf systems can solely be ensured with the exclusive use of Knauf system components, or other products expressly recommended by Knauf. The validity and up-to-datedness of the stated proofs have to be considered.

Notes on fire resistance

The specifications marked with **plus** offer additional application options, which are not directly included in the Certificate of Usability. On the basis of our technical assessments, we assume that these marked design solutions can be assessed as a non-significant divergence. We can make the documentation on which this assessment is based, such as surveyors' reports or technical assessments, available to you together with the Certificate of Usability on request. We recommend that a non-significant divergence be coordinated and authorised in advance in consultation between the persons responsible for fire resistance and/or the relevant authorities.


Knauf WARM WALL Natur T – The The Natural Insulation Façade in Timber Construction

Knauf WARM WALL Natur T – The Natural Insulation Façade in Timber Construction – is a building authority approved external thermal insulation composite system (ETICS) in timber construction made of ecological wood fibre façade boards (directly clad), manufactured according to EN 13171. The peripheral tongue and groove edge type of the boards prevent heat losses in the joint area and guarantee a safe and fast insulation panel bond with a flat surface. WARM WALL Natur T can be utilized up to building class 3 without any special measures. The system can also be applied for other building classes when fire protection concepts are taken into consideration.

Properties


- ETICS reaction to fire: flammable (building material class B2), see table [Page 13](#)
- Highly permeable as well as good regulation of moisture
- High heat storage capacity for protection against summer heat
- Good thermal and sound insulation properties
- Insulation material thickness: certified up to maximum 80 mm

Timber frame construction



Knauf WARM WALL Natur T – The Natural Insulation Façade in Timber Construction (continuation)

Solid wooden substrate



Solid wooden substrate

AGEPAN® THD Putz 050
(Wood fibre insulation panel
with peripheral tongue and
groove edge)

System dowels or broadback
staples

Basecoat, mesh reinforcement,
Primers

Finish coat and paint if
necessary

Plinth connection with plinth
connection profile and plinth
push on profile or thermal
bridge free plinth connection
with Sockel-Abschlussprofil
Peri plinth profile and if
necessary Peri mounting rail

Plinth insulation panel

System overview

Knauf System	WE203Ta.de WARM WALL Natur T Mineral based	WE203Tc.de WARM WALL Natur T Mineral/Organic
Description	Natural rendering mortar made of high-quality mineral-based raw materials optionally available with marble grains. Robust, durable, open to diffusion with variable render surface. Combined with a mineral reinforcement (basecoat) layer.	Organically bonded finishing plaster for a more intensive range of colour shades. Combined with a mineral reinforcement (basecoat) layer.
Reaction to fire/building material class ETICS	Flammable, B2 (see Page 13)	
Maximum insulation material thickness t	Up to 80 mm	
Plaster system layer thickness (reinforcement layer and finish coat)	8.5 – 15 mm	8.5 – 13 mm
Façade		
Insulation materials WF	AGEPAN® THD Putz 050	
Fasteners	Schraubdübel STR H dowels, Schraubdübel 6H dowels, broadback staples (steel staples $b_p \geq 27.5$ mm wide, $t_n \geq 2.0$ mm, $l_n \geq 75$ mm, anchoring depth at least 30 mm, made of stainless steel acc. to EN 14592)	
Basecoat	SM700 Pro, Luis	
Reinforcement mesh	4x4 mm, 5x5 mm	
Primers	Isogrund (recommended)	Quarzgrund pro
Finish coat	SM700 Pro SP 260 Pro RP 240 Noblo Noblo Filz MineralAktiv Scheibenputz floated render	Conni S Addi S
Paint coats	Siliconharz-EG-Farbe paint ¹⁾ Autol, Autol TSR Minerol MineralAktiv Fassadenfarbe paint ²⁾	Siliconharz-EG-Farbe paint ¹⁾ Autol, Autol TSR MineralAktiv Fassadenfarbe paint
Plinth/splash water area		
Adhesive	Sockel-SM Pro or Sockel-SM, SM700 Pro, Luis	
Insulation material	Sockeldämmplatte 032, Sockeldämmplatte 035	
Plinth connection (with recessed plinth)	Sockel-Abschlussprofil Peri plinth profile (free of thermal bridges) and if necessary Peri installation rail, plinth profile and push on plinth profile	
Basecoat	Sockel-SM Pro or Sockel-SM, SM700 Pro, Luis	
Mesh reinforcement, primer, finish coat and decorative coat	As with façade, Butz, Sockel-SM Pro, Sockel-SM	
Plaster seal / moisture protection	Sockel-Dicht (with Sockel-SM Pro as a basecoat and render finish with a total thickness ≥ 7 mm not required)	

1) Coat with Siliconharz-EG-Farbe paint is unnecessary when applied on MineralAktiv Scheibenputz floated render and Conni S.

2) Required on MineralAktiv Scheibenputz floated render.

System variants

New constructions – wooden frame constructions

Scheme drawing	Approved substrate
	<p>Permissible directly on the load bearing timber frame construction. The application of ETICS on board materials is not permissible.</p>

New construction – solid wooden substrate

Scheme drawing	Approved substrate
	<ul style="list-style-type: none"> ■ Solid wood exterior wall components made of Lignotrend elements acc. to abZ/aBG Z-9.1-555 ■ Wood material exterior wall components made of SWISS KRONO MAGNUMBOARD® OSB elements acc. to ETA-13/0784 ■ Solid timber panels (three- and five-layer boards made of softwood) acc. to EN 13986, type SWP/2 or SWP/3 ■ Stacked timber elements acc. to National Technical Approval or European Technical Assessment ■ Cross-laminated timber acc. to National Technical Approval or European Technical Assessment ■ Glulam and stacked wood laminate elements acc. to EN 14080

Old construction – special applications following Z-33.47-673




Scheme drawing	Approved substrate
<p>Coordination with the planning office is generally necessary.</p>	<p>Existing walls can be thermally retrofitted with a façade as a wood frame construction with WARM WALL Natur T, e.g.</p> <ul style="list-style-type: none"> ■ Masonry ■ Timber framing

1) Cross-section of wooden studs as well as fixing with building authority approved frame dowels or connectors according to the structural certificate.

t = insulation material thickness

s = anchoring depth in load-bearing substrate

Insulation material

Insulation material	Description	Rated value of thermal conductivity λ_B W/(m·K)	Board format (cover dimension) w x l mm	Application type	Insulation material thickness mm
Façade					
	AGEPAN® THD Putz 050 Single layer wood fibre façade board with peripheral tongue and groove edge	0.049	600 x 1890 (585 x 1875)	Acc. to aBG	40 50 60 80
Reveal					
	EPS Standard 035 white	0.035	500 x 1000	WAP / acc. to aBG	20 – 50
	EPS Standard 032	0.032	500 x 1000	WAP / acc. to aBG	20 – 50
Plinth					
	Sockeldämmplatte 035 plinth insulation panel EPS, white	0.035	500 x 1000	PW	30 – 80
	Sockeldämmplatte 032 plinth insulation panel EPS, grey	0.032	500 x 1000	PW	40 – 80

Thermal resistance

Examples

Insulation material	Rated design value of the thermal resistance R in (m ² ·K)/W Insulation thickness t in mm			
	40	50	60	80
AGEPAN® THD Putz 050	0.82	1.02	1.22	1.63

In the table, using the rated thermal resistance as well as the thickness of the insulation material you can read off the rated value of the thermal resistance R. The sum of all thermal resistances (plaster, timber construction, insulation materials, etc.) is added to the sum of the 0.17 (m²·K)/W of both thermal transfer resistances for interior and exterior and delivers the thermal resistance. The inverse value of the thermal transmission resistance is the U value.

Dowels

Schraubdübel STR H dowel, Schraubdübel 6H dowel

Quick fasteners for surface flush installation of wood fibre insulation panels on wooden substrates.

Basecoat

The reinforcement mortar is referred to as basecoat in the approvals and in ETICS is a component of the rendering/plastering system. Its purpose is to protect the ETICS permanently from the effects of weather, to securely incorporate the reinforcement mesh and to form the basis for the subsequent finish coating.

Reinforcement mesh

The reinforcement mesh 4x4 mm and 5x5 mm are high strength, permanent, alkaline resistant reinforcement mesh made of glass fibres with a mesh spacing of 4x4 mm or 5x5 mm. The mesh is resistant to sliding and includes blue markings for mesh overlap indication. In addition to the mesh spacings, both meshes differ in terms of their tensile strengths, the weight per unit area and rigidity. They have the function of a reinforcement to avoid the formation of cracks and prevent the ingress of moisture into the system. The mesh is embedded into the fresh basecoat. The position of the basecoat depends on its thickness.

Finish coat

Noblo Filz

Mineral-based, fine grain finishing plaster with 1.0 or 1.5 mm marble grains for fine sponged surface finishes or as a floated render (1.0 mm).

Noblo, SP 260 Pro, RP 240

Mineral finishing renders as a floated render texture (Noblo and SP 260 Pro) and/or groove render texture (RP 240).

SM700 Pro

The mineral based, universal all-rounder for façades and plinths can be sponge finished or freely-structured as a natural white or coloured top coat.

MineralAktiv Scheibenputz floated render

In a system together with MineralAktiv Fassadenfarbe paint, the mineral floated render offers the highest level of protection against the growth of algae and fungi and caters for the perfect appearance of façades. MineralAktiv Scheibenputz floated render also impresses with its elegant texture.

Conni S

Ready-to-use, paste-like, soiling-resistant silicone resin floated render, highly water-repellent and highly water permeable.

Addi S

Ready-to-use, paste-like, organically bonded and silicone resin reinforced floated render for intensive colour shades. Very extra-hard wearing, water-repellent and water-vapour-permeable.

Sockel-SM Pro, Sockel-SM

System approved and mineral based universal all rounder on a cementitious basis for the plinth area. Use as an adhesive and reinforcing mortar as well as a sponged finish coat. When using Sockel-SM Pro as a basecoat and render finish with a total render thickness ≥ 7 mm, no additional protection for the render against ground moisture (moisture protection) is necessary.

Butz

Can only be used in the plinth zone. Coloured stone render with washed plaster effect for surface design in areas subject to wear and tear, e.g. plinth surfaces in the splash water zone.

Finish coat (continued)

Characteristics of finish coats for plinths / splash water zone and façade

Characteristics	Mineral-based finishing plasters					Organic finishing plasters		
	Noblo Filz, Noblo, SP 260 Pro, RP 240	SM700 Pro	MineralAktiv Scheibenputz floated render	Sockel-SM Pro	Sockel-SM	Conni S	Butz	Resin plasters Addi S
Binder	Lime cement	Lime cement	Hybrid binder	Cement	Cement	Silicone resin emulsion, dispersion	Silicone resin emulsion, dispersion	Polymer dispersion, silicone resin
Hydrophobic (water-repellent)	••	••	••	••••	•••	••••	••••	•••
Diffusion properties	••••	••••	••••	••	••	•••	••	•
Colour shade range	••	••	••	•	•	•••	••	••••
Resistance to soiling	••••	••••	••••	••••	••••	••••	••••	•••
Plinth/splash water area	••	••••	••	••••	••••	•••	••••	••

- Ideal
- Ideal to very well suited
- Very suitable
- Suitable

Application of finish coats for plinths / splash water zone and façade

Criteria	Mineral-based finishing plasters						Organic finishing plasters		
	Noblo Filz	Noblo, SP 260 Pro	RP 240	SM700 Pro	MineralAktiv Scheibenputz floated render	Sockel-SM Pro, Sockel-SM	Conni S	Butz	Resin plasters Addi S
Surfaces									
Sponged texture	•			•		•			
Freely styled texture	•			•				•	
Textured floated render	•	•			•		•		•
Textured groove render			•						
Application									
By machine	•	•	•	•	•	•	•		•
By hand	•	•	•	•	•	•	•	•	•
Order information									
Bucket (paste-like)					•		•	•	•
Bagged material	•	•	•	•		•			

Paint coats

Siliconharz-EG-Farbe paint

Siliconharz-EG-Farbe paint is especially suitable for equalisation (single coat) of mineral finishing coats with the same colour shade as the render and the paint. Suitable for equalisation of drying-related, weather-related or application-related differences in the colour shade on the finishing coat.

Autol

Autol is a highly permeable, matt, premium silicon resin self-cleaning effect façade paint. It is ideally suited as two paint coats on mineral and organically bound renders, as well as a top coat in case of different shades of finishing coat and paint. A strong reduction in the adhesion of dirt particles facilitates wash-off of dirt and soiling by the action of precipitation.

Autol TSR

Autol TSR is a highly permeable, matt, silicon resin self-cleaning effect façade paint. Reflection-optimised, resulting in reduced heat-up due to solar radiation and increased resistance to cracking on the substrate. It is used on new, pure white rendering/plastering systems when the colour shade of the

finish coat has a luminosity of < 20.

Minerol

Minerol is a highly permeable, matt, premium silicate façade paint with organic stabilisers. It is ideally suited as a texture-retaining two coat paint on mineral substrates. Minerol bonds by silification with the substrate and is an ideal coating on mineral renders in case of different shades of finishing coat and paint.

MineralAktiv Fassadenfarbe paint

MineralAktiv Fassadenfarbe paint is a texture preserving, mineral façade paint on a hybrid binder basis without addition of film preservation. The optimised moisture management ensures that MineralAktiv Fassadenfarbe façade paint in a system with MineralAktiv finish coats is ideal in preventing growth of algae and mould. It has a high yield and an elegant mineral appearance.

Comparison of Knauf façade paints

Criteria	Mineral based		Organic	
	Silicate based dispersion Minerol	Hybrid façade paint MineralAktiv Fassadenfarbe paint	Silicone resin paints Autol, Autol TSR	Siliconharz-EG-Farbe paint
Binder	Potassium silicate, dispersion	Hybrid binder	Silicone resin emulsion, dispersion	Silicone resin emulsion, dispersion
Hydrophobic (water-repellent)	●●●	●●●	●●●●	●●●●
Diffusion properties	●●●●	●●●●	●●●●	●●●
Colour shade range	●●	●●	●●●	●●
Resistance to ageing	●●●●	●●●●	●●●●	●●●●
Hiding power	●●●	●●●●	●●●●	●●●

- *Ideal*
- *Ideal to very well suited*
- *Very suitable*

Knauf Farbcenter (colour center)

The Knauf Farbcenter provides information on the feasibility and luminosity of colour shades for Knauf paints and plasters: knauf.de/farbcenter.

Explanation of colour code

B P 2 5 7

- └ Luminosity range (here: 70 to 79)
- └ Brightening
- └ Greying
- └ Colour shade with English designation abbreviations (in this case: Blue Purplish)

U values and parameters for the protection against summer heat with WARM WALL Natur T

Examples

Studs w x h mm	Infill insulation λ_B W/(m·K)	With WARM WALL Natur T exterior insulation												Calculation without correction for fasteners			
		Insulation material thickness t 40 mm				50 mm				60 mm				80 mm			
		U value total W/(m ² ·K)	φ^1 h	TAR ²⁾	TAD ³⁾	U value total W/(m ² ·K)	φ^1 h	TAR ²⁾	TAD ³⁾	U value total W/(m ² ·K)	φ^1 h	TAR ²⁾	TAD ³⁾	U value total W/(m ² ·K)	φ^1 h	TAR ²⁾	TAD ³⁾
60 x 100	0.040	0.312	6.8	0.295	3	0.296	7.9	0.245	4	0.277	8.5	0.216	5	0.249	10.1	0.148	7
	0.035	0.291	7.1	0.262	4	0.276	8.1	0.225	4	0.259	8.8	0.192	5	0.234	10.4	0.131	8
	0.032	0.279	7.2	0.252	4	0.263	8.0	0.218	5	0.250	8.9	0.185	5	0.226	10.5	0.127	8
60 x 120	0.040	0.276	7.1	0.258	4	0.263	8.2	0.213	5	0.248	8.8	0.189	5	0.225	10.4	0.130	8
	0.035	0.256	7.5	0.225	4	0.245	8.4	0.194	5	0.231	9.2	0.163	6	0.211	10.8	0.114	9
	0.032	0.245	7.5	0.217	5	0.233	8.3	0.189	5	0.222	9.2	0.160	6	0.203	10.8	0.110	9
60 x 140	0.040	0.245	7.4	0.228	4	0.237	8.6	0.187	5	0.222	9.1	0.168	6	0.203	10.7	0.115	9
	0.035	0.226	7.8	0.196	5	0.220	8.8	0.170	6	0.207	9.6	0.145	7	0.190	11.2	0.099	10
	0.032	0.219	7.7	0.190	5	0.209	8.6	0.166	6	0.200	9.5	0.141	7	0.184	11.1	0.096	10
60 x 160	0.040	0.225	7.6	0.203	5	0.216	8.9	0.166	6	0.205	9.4	0.150	7	0.189	11.0	0.103	10
	0.035	0.207	8.2	0.173	6	0.199	9.1	0.149	7	0.191	9.9	0.128	8	0.176	11.5	0.087	11
	0.032	0.197	8.0	0.168	6	0.189	8.9	0.147	7	0.182	9.8	0.125	8	0.169	11.4	0.085	12
60 x 180	0.040	0.205	7.9	0.183	5	0.198	9.2	0.148	7	0.189	9.6	0.135	7	0.175	11.3	0.092	11
	0.035	0.189	8.5	0.154	7	0.183	9.4	0.133	8	0.175	10.2	0.113	9	0.163	11.9	0.077	13
	0.032	0.180	8.3	0.150	7	0.173	9.2	0.131	8	0.167	10.0	0.111	9	0.156	11.7	0.076	13
60 x 200	0.040	0.189	8.1	0.165	6	0.183	9.5	0.133	8	0.175	9.9	0.122	8	0.163	11.5	0.084	12
	0.035	0.174	8.8	0.137	7	0.169	9.8	0.119	8	0.162	10.6	0.101	10	0.152	12.2	0.069	15
	0.032	0.165	8.5	0.135	7	0.160	9.4	0.118	8	0.154	10.3	0.100	10	0.145	12.0	0.068	15


1) Phase lag

2) Temperature amplitude ratio

3) Temperature amplitude damping

The temperature amplitude ratio (TAR) describes the maximum temperature fluctuation (amplitude) on the interior room-side construction component surface to the maximum temperature fluctuation on the exterior construction component surface. The lower the TAR value, the higher the attenuation. The inverse value is called the temperature amplitude damping (TAD). The phase lag is the period between the occurrence of the highest temperature on the exterior outer surface of a building component until the highest temperature is achieved on the interior, and depends on the heat retention capacity of the building component layers. A phase lag of more than 10 hours should be pursued.




Design example



Fire resistance requirements acc. to building regulation bye-laws

The demands on the reaction to fire of the façade lining are defined in the state building codes (LBO) and the corresponding fire prevention regulations of the German states. They are differentiated in dependence on the building height and/or building classes.

Additional special guidelines or regulations must be observed for special constructions and buildings such as hospitals, meeting halls, residential care homes, schools, shopping centres, etc. ETICS in scenarios such as firewalls building party walls, access galleries, escape routes, fire service passage routes, etc. must be designed as non-combustible according to the state building codes (building material class A according to DIN 4102-1).

Height range	Upper edge of the floor ¹⁾	Required fire behaviour of ETICS	Building material class of ETICS Acc. to DIN 4102-1	
	Building class 1 – 3 (Low height buildings)	$h = 0 - 7 \text{ m}$	Flammable	B2
	Building class 4 – 5 (Medium height buildings)	$h > 7 - 22 \text{ m}$	Not easily flammable	B1
	High-rise buildings	$h > 22 \text{ m}$	Non-combustible	A

1) The specified heights are defined differently in the individual German states. They can be found in the respective state building codes. The height specifications refer to the dimension of the upper edge of the highest floor on which common rooms can be built, measured from the average terrain height (clause 2, paragraph 3 of the Musterbauordnung [German model building code] as well as the respective state building code).

Reaction to fire of WARM WALL Natur T in Timber Construction

Insulation material thickness t	System	Reaction to fire/building material class ETICS
Up to 80 mm	Mineral Mineral / organic	Flammable B2 (acc. to DIN 4102-1)


Method for determination of wind loads

For use with	Practice-based method Acc. to the recommendations of the VDPM ¹⁾ and the DIBt ²⁾ (Germany)	Simplified method Acc. to EN 1991-1-4 and EN 1991-1-4/NA	Standard method Acc. to EN 1991-1-4 and EN 1991-1-4/NA
Building height	≤ 25 m	≤ 25 m	Not specified
Wind zone	1 to 3	1 to 4	1 to 4
Building layout	Rectangular	Rectangular	Any
Height / width ratio	≤ 2	≤ 2	Any
Elevation of site	≤ 800 m above sea level, flat terrain	≤ 800 m above sea level, flat terrain	Any

1) Verband für Dämmsysteme, Putz und Mörtel e. V. - Federation for Insulation Systems, Plaster and Mortar


2) Deutsches Institut für Bautechnik - German Institute for Civil Engineering

Procedure for determining the quantity and length of fasteners



Determination of wind loads

Wind zones acc. to EN 1991-1-4/NA



Determination of wind loads (continuation)

Wind suction forces w_{ek} in kN/m^2 acc. to EN 1991-1-4 and EN 1991-1-4/NA acc. to the simplified method


Wind zone	Region	Wind suction forces w_{ek} in kN/m^2					
		Building height					
		0 to 10 m		0 to 18 m		0 to 25 m	
		Fringe A	Zone B	Fringe A	Zone B	Fringe A	Zone B
1a	Inland	0.738	0.550	0.959	0.715	1.106	0.825
2a	Inland	0.959	0.715	1.180	0.880	1.328	0.990
2b	Coast and Baltic sea islands	1.245	0.935	1.475	1.100	1.623	1.210
3a	Inland	1.180	0.880	1.401	1.045	1.623	1.210
3b	Coast and Baltic sea islands	1.549	1.155	1.770	1.320	1.918	1.430
4a	Inland	1.401	1.045	1.696	1.265	1.918	1.430
4b	North and Baltic sea coasts and Baltic sea islands	1.844	1.375	2.065	1.540	2.286	1.705
4c	North sea islands	2.065	1.540	–	–	–	–

Determination of the width of fringe A

Width of fringe A:
 $1/5 e$ or $1/5 f$

$e = 2 \times \text{height}$ or $e = \text{length}$
 $f = 2 \times \text{height}$ or $f = \text{width}$

The smallest corresponding value is decisive.



Dimensioning of the fasteners and spacings

Table 1: Minimum number of dowels acc. to approval

Wind zone	Region	Minimum number of dowels per m^2	
		Maximum ETICS wind load: 1.60 kN/m^2 Wind loads acc. to simplified method	
		Building height 0 to 10 m Timber frame construction, solid wooden substrate	
		Fringe A	Zone B
1a	Inland	6	5
2a	Inland	6	6
2b	Coast and Baltic sea islands	8	6
3a	Inland	8	6
3b	Coast and Baltic sea islands	8	8
4a	Inland	8	8
4b	North and Baltic sea coasts and Baltic sea islands	–	–
4c	North sea islands	–	–

Dimensioning of the fasteners and spacings (continued)

Table 2: Minimum number of broadback staples acc. to approval

Wind zone	Region	Minimum number of broadback staples per m ² Maximum ETICS wind load: 1.60 kN/m ² Wind loads acc. to simplified method	
		Building height 0 to 10 m Timber frame construction, solid wooden substrate	
		Fringe A	Zone B
1a	Inland	11	10
2a	Inland	11	11
2b	Coast and Baltic sea islands	16	11
3a	Inland	16	11
3b	Coast and Baltic sea islands	16	16
4a	Inland	16	16
4b	North and Baltic sea coasts and Baltic sea islands	–	–
4c	North sea islands	–	–

Selection of the fasteners

Length of the fastener in dependence on the insulation material thickness

Insulation material thickness	Length of the fastener		
	Schraubdübel STR H dowel (acc. to abZ)	Schraubdübel 6H dowel	Broadback staple (acc. to EN 14592)
t mm	s ≥ 30 mm mm	s ≥ 30 mm mm	s ≥ 30 mm mm
40	80	70	75
50	80	90	85
60	100	90	100
80	120	110	110

t = insulation material thickness


s = anchoring depth in load-bearing substrate

Calculation of the length:

Anchoring depth **s** + insulation material thickness **t**

Implemented with perimeter insulation
WE203T.de-SO-V1 Recessed plinth application

Scale 1:10 | Dimensions in mm




Implemented with perimeter insulation (continued)

WE203T.de-SO-V2 Flush plinth application

Application with floor slab

Scale 1:10 | Dimensions in mm




Implemented with perimeter insulation (continued)

WE203T.de-SO-V10 Recessed plinth application

Scale 1:10 | Dimensions in mm

With fire resistance F30, taking consideration of special measures acc. to DIN 68800-2



Extension of the fire resistance Certificate of Usability


- In case of direct fastening of the AGEPAN® THD Putz 050 on the timber studs
- Prior consultation in acc. to [Page 3](#) is recommended.

Implemented with perimeter insulation (continued)

Scale 1:10 | Dimensions in mm


WE203T.de-SO-V13 Recessed plinth application

Taking consideration of special measures acc. to DIN 68800-2



Detail A

Scale 1:5





Note Penetration of the building waterproofing should be avoided.

French door connections

Scale 1:10 | Dimensions in mm

WE203T.de-SO-V5 Recessed plinth application

French door exterior flush with wooden studs, not barrier free



Notes



Take care to ensure fully sealed openings (interface gaps) and ensure that filling is applied under window frames.

The window installation and seals are represented schematically, refer to "Guideline on the installation of windows and doors" from the RAL-Gütegemeinschaft Fenster und Haustüren e.V. (German Quality Assurance Association Windows and Doors) or the guideline "Connection of windows and roller blinds with plaster, drywall and external thermal insulation composite systems" (German only) from the Fachverband der Stuckateure für Ausbau und Fassade Baden Württemberg, Germany. The construction details shown only apply for the implementation of a second water channelling level, e.g. with Knauf WARM WALL window sealing system, see Installation Instructions [P651-A01.de](https://www.knauf-warmwall.de/P651-A01.de).

French door connections (continued)
WE203T.de-SO-V11 Flush plinth application

Scale 1:10 | Dimensions in mm

French door interior flush with wooden studs, barrier free



Notes

Ground level or barrier free entrance from the terrace should be agreed with the contractors. With the regulations governing barrier-free access, the threshold heights and non-slip surfaces, etc. must be observed. Furthermore, the investor must be informed about non-compliance to the regulations as set down in the DIN 18533 in the area of the cross-over between buildings (height at house door or French door maximum 20 mm). Also refer to the BDF leaflet 03-04 "Plinth constructions acc. to DIN 68800-2, classification in usage class GK 0". Refer to the guideline "Façade plinth render/External components" (German only), issued by Fachverband der Stuckateure für Ausbau und Fassade Baden-Württemberg, flat roof guideline of the German roofers association or in individual cases the green roof guideline of the respective associations.

Take care to ensure fully sealed openings (interface gaps) and ensure that filling is applied under window frames.


The window installation and seals are represented schematically, refer to "Guideline on the installation of windows and doors" from the RAL-Gütegemeinschaft Fenster und Haustüren e.V. (German Quality Assurance Association Windows and Doors) or the guideline "Connection of windows and roller blinds with plaster, drywall and external thermal insulation composite systems" (German only) from the Fachverband der Stuckateure für Ausbau und Fassade Baden-Württemberg, Germany. The construction details shown only apply for the implementation of a second water channelling level, e.g. with Knauf WARM WALL window sealing system, see Installation Instructions [P651-A01.de](#).

Window centred with wooden studs

Scale 1:5 | Dimensions in mm


WE203T.de-FE-H1 Horizontal section

Section A




WE203T.de-FE-H2 Horizontal section

Section B (base)



WE203T.de-FE-V1 Vertical section

Section C



To facilitate drainage of any water present, a second water channelling level between the front edge of the façade insulation and the lower side of the window sill may not have any Fugendichtband FD joint sealing tape installed.

Notes

Take care to ensure fully sealed openings (interface gaps) and ensure that filling is applied under window frames.


The window installation and seals are represented schematically, refer to "Guideline on the installation of windows and doors" from the RAL-Gütegemeinschaft Fenster und Haustüren e.V. (German Quality Assurance Association Windows and Doors) or the guideline "Connection of windows and roller blinds with plaster, drywall and external thermal insulation composite systems" (German only) from the Fachverband der Stuckateure für Ausbau und Fassade Baden Württemberg, Germany. The construction details shown only apply for the implementation of a second water channelling level, e.g. with Knauf WARM WALL window sealing system, see Installation Instructions [P651-A01.de](https://www.knauf-insulation.com/P651-A01.de).

Window exterior flush with wooden studs

Scale 1:5 | Dimensions in mm


WE203T.de-FE-H3 Horizontal section

Section D




WE203T.de-FE-H4 Horizontal section

Section E (base)



WE203T.de-FE-V2 Vertical section

Section F



To facilitate drainage of any water present, a second water channelling level between the front edge of the façade insulation and the lower side of the window sill may not have any Fugendichtband FD joint sealing tape installed.



Notes Take care to ensure fully sealed openings (interface gaps) and ensure that filling is applied under window frames.
The window installation and seals are represented schematically, refer to "Guideline on the installation of windows and doors" from the RAL-Gütegemeinschaft Fenster und Haustüren e.V. (German Quality Assurance Association Windows and Doors) or the guideline "Connection of windows and roller blinds with plaster, drywall and external thermal insulation composite systems" (German only) from the Fachverband der Stuckateure für Ausbau und Fassade Baden Württemberg, Germany. The construction details shown only apply for the implementation of a second water channelling level, e.g. with Knauf WARM WALL window sealing system, see Installation Instructions [P651-A01.de](#).

Connection to window sill side section

Scheme drawings | Dimensions in mm

WE203T.de-FE-V3 Connection to window sill including edge profile with slide function



Section G



Design of the front edge of the reveal board

WE203T.de-FE-V4 Connection to window sill – subsequent window sill installation

Section H



Design of the front edge of the reveal board

Notes

The construction details shown only apply for the implementation of a second water channelling level, e.g. with Knauf WARM WALL window sealing system, see Installation Instructions [P651-A01.de](https://www.knauf-etics.com/P651-A01.de).

At the foot of the reveal insulation panel as well as the render system, a joint is mandatory in the connection area to the window sealing corner/window sealing membrane, to prevent waterlogging underneath the reveal board. This is achieved by attachment of the joint sealing tape FD to the base of the reveal board.

When retrofitting the window sill, do not apply full surface adhesive to the sliding closure to guarantee the water flow direction of the window sill front edge.

See also the video "Knauf – Abdichtung für Fenster bei WDVS" (German) (*Sealing for windows with ETICS*) at: [youtube.com/knauf](https://www.youtube.com/knauf)

Connection to window sill side section (continued)

Recommendation for the lateral render spacing for window sills with edge profile

Window sill colour	Window sill length m	Expected movement mm	Lateral plaster spacing	
			Edge profile without slide function mm	Edge profile with slide function ¹⁾ mm
Natural, white	1	± 0.5	≥ 1	≥ 1
	3	± 1.5	≥ 2	≥ 1
Dark	1	± 1.0	≥ 2	≥ 1
	3	± 2.5	≥ 3	≥ 1



1) The constraint-free movement absorption between the edge profile and window sill must provide at least the expected range of motion.

The installation of window sills with edge profile featuring a slide function; recommended when retrofitting window sills with sliding closures.

Connection to sun screening

Scale 1:10 | Dimensions in mm

WE203T.de-FE-V5 Projection roller blind unit




Notes	When installing the projection roller blind unit, a driving-rain proof application should be observed (connection of the plaster façade with Fugendichtband FD joint sealing tape).
	Ensure that all openings (interface gaps) are sealed.


The window installation and seals are represented schematically, refer to "Guideline on the installation of windows and doors" from the RAL-Gütegemeinschaft Fenster und Haustüren e.V. (German Quality Assurance Association Windows and Doors) or the guideline "Connection of windows and roller blinds with plaster, drywall and external thermal insulation composite systems" (German only) from the Fachverband der Stuckateure für Ausbau und Fassade Baden Württemberg, Germany.

Connection to sun screening (continued)
WE203T.de-FE-V6 Integrated roller blind unit

Scale 1:10 | Dimensions in mm



WE203T.de-FE-V7 Roller blind



Notes


Ensure that all openings (interface gaps) are sealed.

The window installation and seals are represented schematically, refer to "Guideline on the installation of windows and doors" from the RAL-Gütegemeinschaft Fenster und Haustüren e.V. (German Quality Assurance Association Windows and Doors) or the guideline "Connection of windows and roller blinds with plaster, drywall and external thermal insulation composite systems" (German only) from the Fachverband der Stuckateure für Ausbau und Fassade Baden Württemberg, Germany.

Connections to roof


Scale 1:10 | Dimensions in mm

WE203T.de-DA-V1 Eaves connection to roof weatherboarding



WE203T.de-DA-V3 Connection to rising wall - dormer wing

With metal connection mesh profile



Note


Observe guideline "Metallanschlüsse an Putz und Wärmedämm-Verbundsysteme - Metal connections to render and external thermal insulation composite systems", (German only) from the Fachverband der Stuckateure für Ausbau und Fassade Baden Württemberg, Germany as well as the DIN 18531.

Connections to roof (continued)


Scale 1:10 | Dimensions in mm

WE203T.de-DA-V6 Pitched roof connection to rising wall

With metal connection mesh profile



WE203T.de-DA-V5 Bargeboard connection



Note


Observe guideline "Metallanschlüsse an Putz und Wärmedämm-Verbundsysteme - Metal connections to render and external thermal insulation composite systems", (German only) from the Fachverband der Stuckateure für Ausbau und Fassade Baden Württemberg, Germany as well as the DIN 18531.

Expansion and connection joints

Scale 1:5 | Dimensions in mm


WE203T.de-FU-H1 Building Party Wall – Semidetached house

Fire flashover area with Knauf Insulation Tektalan A2-FP/HB



WE203T.de-FU-H2 Connection to existing constructional component

Fire flashover area with Knauf Insulation Tektalan A2-FP/HB




Note

The application in terms of materials and dimensions is based on the guidelines of the applicable state building code. An existing fire protection concept must be observed.

Connection to building corner

Scale 1:5 | Dimensions in mm


WE203T.de-EX-H1 Connection to building corner



Junction between stories

Scale 1:10 | Dimensions in mm

WE203T.de-EX-V1 Connection to junction between stories




Vertical extension

Scale 1:10 | Dimensions in mm

WE203T.de-EX-V2 Vertical extension on existing storey

Existing building not remodelled



Preconditions

Protect the insulation panels against moisture.

All connections and detail features must be clarified before application.

All substrates must be stable, dry and even. The construction timbers or exterior wall components must have a moisture level in the wood of $\leq 20\%$. The substrate must be protected against detrimental moisturization before the application of ETICS.

Rising damp may not be present. Plan all applied connections as driving-rain proof with Fugendichtband FD joint sealing tape. When using driving-rain proof window connection profiles, back with additional FD joint sealing tape. Ensure that all openings (interface gaps) are sealed.

The internal plastering and screed works as well as the introduction of loose infill insulation should be completed and the components should be dry enough so that an excessive accumulation of moisture is avoided.

The contractor is solely responsible for inspecting the condition of the substrate and the on-site conditions. The ambient temperature, substrate and material temperature must be at least $+5\text{ }^{\circ}\text{C}$ and may not exceed $+30\text{ }^{\circ}\text{C}$ during the entire application, drying and setting phase.

Stored insulation materials on building sites must be protected against moisture and direct sunlight. When glueing and applying plaster, suitable protection measures against precipitation and UV-radiation on the façade must be provided.

Only cold, clean water (drinking water quality) may be used as mixing water.

Water up to a temperature of $+30\text{ }^{\circ}\text{C}$ may be used on building sites in spring and autumn.

Cover or apply a watertight covering to easily-soiled building components (e.g. window sills) prior to application. Observe the Code of Practice "Abklebe- und Abdekarbeiten für Maler- und Stuckateurarbeiten - Masking and covering for painting and stucco work" issued by the German Bundesverband Ausbau und Fassade. Protect surfaces from precipitation and direct sunlight.

Please note that with the existing construction type, movements may occur due to

- drying out of materials applied when damp,
 - thermal and moisture deviations within the building materials and the corresponding shrinkage and expansion behaviour,
 - dynamic deformation from horizontal loads (wind load),
- as well as swelling of the wood fibre insulation panels due to extremely high levels of diffusion. These influences may cause stresses in the rendering that may lead to hairline cracks in individual cases.

Building expansion joints must be implemented in ETICS including the cladding and designed accordingly so that the same movement is possible at the same location without any hinderance. The joints must be sealed to be driving-rain proof. The ETICS is unsuitable for exposure to compressive loads due to deformation in the substructure. As long as this cannot be excluded with certainty, suitable measures (e.g. expansion joints) must ensure that they can be accepted.

Machine technology from Knauf PFT for the application of ETICS

Product	Mixing pump/ feed pump	Stator/ rotor	Mortar hoses	Wet mortar pumping distance
Bonding and reinforcement mortar				
SM700 Pro	G 4	D4-3 with Rotoquirl	Ø 25 mm	Up to 30 m
	RITMO L plus	B4-2L with Rotomix	Ø 25 mm	Up to 20 m
Sockel-SM Pro, Sockel-SM	G 4	D4-3 with Rotoquirl	Ø 25 mm	Up to 30 m
	RITMO L plus	B4-2L with Rotomix	Ø 25 mm	Up to 15 m
Luis	G 4	D4-3 1/2 capacity	Ø 25 mm	Up to 40 m
Finishing plasters				
Mineral, thin-layer finishing coats (e.g. SP 260 Pro, RP 240 etc.)	G 4	D4-3	Ø 25 mm	Up to 30 m
	RITMO L plus	B4-2L	Ø 25 mm	Up to 20 m
Paste-like finishing plasters (e.g. Addi S, Conni S, MineralAktiv Scheibenputz floated render)	SWING	C4-2	Ø 25 mm	Up to 20 m
	RITMO L plus	B4-2L	Ø 25 mm	Up to 20 m

For further information on machine engineering see: pft.net

Insulation material – Bonding

Plinth and splash water zone

Inspect / supplement the building waterproof sealing before insulation work. The application of ETICS in the splash water zone is only permissible, if it can be assured that the thermal insulation material is not exposed to moisture. Otherwise the thermal insulation material in this zone must be replaced by a suitable material (e.g. Knauf plinth insulation panel or EPS insulating material). A plinth insulation panel must be used in the plinth or splash water zone.

Adhesively bond plinth insulation panels using adhesive mortar on mineral or bituminous waterproofing of buildings. The adhesive application is across the entire surface or using an edge ribbon and dab bonding method with an adhesive surface of at least 40 %. The lower edge of the plinth insulation panel must have a continuous strip applied at least 50 mm wide. The lower edge of the plinth insulation panel can be taper cut with a minimal integration depth in the soil (up to 500 mm under the ground level), according to guideline "Façade plinth render/External components" (German only), issued by Fachverband der Stuckateure für Ausbau und Fassade Baden-Württemberg.

Allow a setting time of at least 48 hours before continuing work.

Adhesive bonding on bituminous substrates

In case of mineral adhesives (not necessary with Sockel-SM Pro), apply Sockel-Dicht on two component, bituminous substrates as a bonding layer and roughen the surface with a broom. Allow to dry and set fully before continuing. Insulation material from 150 mm above the edge of the ground line requires additional dowels.

Further information

For further information on the installation and application of insulation panels and plaster system in the plinth area see [Pages 34 to 44](#).

Observe the following guidelines:

- Guideline "Façade plinth render/External components" (German only), issued by Fachverband der Stuckateure für Ausbau und Fassade Baden-Württemberg
- DIN 18533
- DIN 68800-2
- BDF leaflet 03-04 "Plinth constructions acc. to DIN 68800-2" of the German Bundesverband Deutscher Fertigung e. V.
- DHV leaflet "Praxisgerechte Sockelausbildung - practical plinth design" of the German association Deutschen Holzfertigung-Verbandes e. V.
- "Informationsdienst Holz – Holzrahmenbau - information service on wood and wood frame construction" from the German Informationsvereins Holz e. V.

Insulation material – application

The substrate must be stable, dry, even and sufficiently wide enough for attachment. The construction timbers or exterior wall components must have a moisture level in the wood of $\leq 20\%$.

Apply the insulation panels when dry (board moisture $< 13\%$ by mass), dust free according to manufacturers guidelines. Observe the notes on exposure to outdoor weather (see [Page 38](#)). Dry cleaning of soiled surfaces only. The boards must be worked in the dry state. Should there be slight damage on the board ends, the loose fibre materials must be removed before joining the boards to ensure tight joints.

The substrate temperature must be $\geq 0\text{ }^{\circ}\text{C}$ when placing a dowel. Back-ventilation of the system level should be avoided both with the installation on a wooden frame as well as on surface substrates, so that the boards do not warp and curl due to different levels of moisture on both surfaces. This can lead to problems associated with deformation and imperfections and can impair the airtightness of the ETICS reducing the effectiveness of the insulation.

Install the plinth connection end profile horizontally and fix using suitable fasteners at spacings of approx. 300 mm. Connect the joints and the plinth connection end profiles with H connectors. Provide the outside corners with the appropriate mitring. Push on the plinth profile made of plastic with drip edge and integrated reinforcement mesh strips on the plinth connection end profile ensuring joint offsetting to the plinth connection profile.

When connecting perimeter/plinth insulation panels with recessed plinth to existing ETICS or when using a plinth connection end profile, a joint sealing tape FD is inserted between the perimeter/plinth insulation panel and plinth connection end profile. If the ETICS are applied on existing perimeter / plinth insulation panels, use of a Peri plinth connection profile is recommended. Application of a joint sealing tape is unnecessary. As an alternative for a thermal-bridge free plinth connection, apply the Peri mounting rail with a suitable fastener (see [Page 43](#)). Peri plinth connection profile is inserted between the perimeter insulation and the façade insulation panel. Consider the offset between the Peri plinth end profile and insulation panel butt joint.

Apply insulation panels directly onto the wooden construction. Bed the boards aligned with the tongue pointing upwards and joints staggered by $\geq 300\text{ mm}$ on the plinth connection end profile or on the Peri mounting rail (cut off the groove of the first insulation panel row or fill with insulation material strips). The highly compacted cover layer with the stamp is the exterior side to be plastered. Avoid cross joints, e.g. on opening corners. At corners of openings (windows, doors), the insulation panels are to be laid in such a way that the butt joints are preferably not present in the immediate corner.

There may be no offsets, open butt joints, cross joints and bed joints, flaws or unevenness present that exceed the specifications of the DIN 18202 "Tolerances in building construction". Furthermore, there may be no unsupported joints with end to end edges in the surface and the substrate may not deform when the boards are pressed on.

The application of AGEPAN® THD Putz 050 on board materials is not permissible, e.g. on GKB/GKF gypsum boards or OSB boards.

Minimum quantity and arrangement of the fasteners acc. to the German National Technical Approval / type approval Z-33.47-673 (see [Pages 15 to 16](#)). The wind loads result in acc. with EN 1991-1-4 and EN 1991-1-4/NA. The simplified method in acc. with [Pages 14 to 16](#) can be applied with the corresponding conditions.

Every insulation panel must be fixed to at least two wooden studs (spacing of studs $\leq 625\text{ mm}$) using at least 6 broadback staples per stud at vertical spacings $\leq 100\text{ mm}$ and with a staple angle of 30 ° to 60 ° or using at least 3 dowels per stud. Apply staples and dowels so that they are flush with the surface and consider the required perimeter spacings in accordance with EN 1995-1-1 with EN 1995-1-1/NA. Placement of the fastener on the board joint is not permissible. The anchoring depth is at least 30 mm in all cases. Other fasteners not specified in the National Technical Approval / type approval Z-33.47-673 are not permissible.

If a board joint is required on the wooden stud, AGEPAN® THD Putz 050 should create a butt joint and the staples should be applied directly on the wooden stud on the left and right beside the board joint arranged with a minimum spacing to the middle of the staple of 20 mm (stud width minimum 80 mm with inclined staple arrangement, see scheme drawing on [Page 37](#)).

Any joints that may occur up to a maximum width of 5 mm can be sealed with WF Adheseal. In case of joints exceeding 5 mm width, use make-up pieces made of equivalent insulation material and glue them with a frictional bond using WF Adheseal. Grind any board joint surface unevenness smooth after application. Completely remove any grinding remnants (dust-free).

Insulation material – application (continued)

Corner grooving is unnecessary. Create a butt joint on front ends (cut back the tongues or grooves).

The wood fibre insulation panels may be applied up to 300 mm above the ground line. The DIN 68800-2 must be observed if the spacing to the ground line is reduced, see details on [Pages 19 to 22](#).

Connections to adjacent constructional components should be made driving-rain proof with joint sealing tape FD. Connections, e.g. to window sills, should generally be carried out so that a second water draining or sealing level is provided (see installation instructions [P651-A01.de](#)). In order to allow any resulting water to drain to the exterior, no joint sealing tape FD may be used between the front edge of the façade insulation and the window sill with the second water channelling level. Furthermore, window sills must be rain-proof, e.g. with the aid of plastered in edge profiles featuring a sliding function.

Plinth and splash water zone

Apply additional constructional, mechanical fixing of the plinth insulation panels from a height of 150 mm measured above the edge of the ground line, e.g. for bituminous or painted substrates with general building authority approved dowels (2 dowels per board).

Notes


Wet, soiled or damaged insulation panels may not be installed.

For rating and selection of the fasteners, see [Pages 14 to 16](#).


Furthermore, the specifications on material and application of the insulation panels must be observed:
sonaearauco.com

Non-supported joints with tongue and groove

Staples




Dowels




Fix the insulation panels to at least two wooden studs, refer to tables for the required number of fasteners on [Pages 15 to 16](#)

Window and door openings



Avoid cross joints

Corner configuration



Insulation material – application (continued)

Fasteners

Scheme drawings

Timber frame construction	Solid wooden substrate	Remarks
Dowels Schraubdübel STR H (acc. to abZ), Schraubdübel 6H		
		<ul style="list-style-type: none"> Always apply dowels to the board surface
Broadback staples (acc. to EN 14592)		
		<ul style="list-style-type: none"> Always apply staples to the board surface Apply staples flush to the boards

t = insulation material thickness

d_n = rated diameter of a staple arm ≥ 2.0 mm

s = anchoring depth ≥ 30 mm in load-bearing substrate

The EN 1995-1-1 and EN 1995-1-1/NA apply for the required perimeter spacings.

Insulation material – application (continued)

Dowels



Determination of the wind load, the number of dowels and dowel arrangement schemes at: knauf.de/duebelrechner

Timber frame construction – Broadback staples

Scheme drawings | Dimensions in mm

Minimum required quantity according to the rating of the fasteners Pages 14 to 16	Cover dimension 585 mm x 1875 mm	Remark
10 – 16 staples/m ²		<p>The vertical permissible stud spacings in accordance with the approval must be observed. Each insulation panel has to be attached to at least two wooden studs with 6 staples per stud (18 staples/board with a board size of 1.1 m²)</p>

Notes

The specified dimensions are based on the insulation panel edge/distance between centres of the staples. Placement of the fastener on the board joint is not permissible.

Board joints on the wooden studs must be applied as butt joints.

If the staples are not arranged at an angle of 30° – 60° to the wooden studs with a butt joint, the number of staples increases by 30 %.

Required perimeter spacings acc. to EN 1995-1-1 and EN 1995-1-1/NA.

For rating and selection of the fasteners, see [Pages 14 to 16](#).

Insulation material – application (continued)

Solid wooden substrate – broadback staples

Scheme drawings | Dimensions in mm

Minimum required quantity according to the rating of the fasteners Pages 14 to 16	Cover dimension 585 mm x 1875 mm	Remark
10 – 11 staples/m ²		<p>The vertical permissible stud spacings in accordance with the approval and sufficient fastening of at least the vertical panel edges must be observed.</p> <p>18 staples/panel are required with a board size of 1.1 m².</p>
16 staples/m ²		<p>The vertical permissible stud spacings in accordance with the approval and sufficient fastening of at least the vertical panel edges must be observed.</p> <p>22 staples/panel are required with a board size of 1.1 m².</p>

Notes	<p>The specified dimensions are based on the insulation panel edge/distance between centres of the staples. Placement of the fastener on the board joint is not permissible.</p> <p>Required perimeter spacings acc. to EN 1995-1-1 and EN 1995-1-1/NA.</p> <p>For rating and selection of the fasteners, see Pages 14 to 16.</p>
--------------	--

Insulation material – Exposure to outdoor weather

Boards may be exposed to outdoor weather for a maximum of 30 days. A prerequisite is the professionally applied sealing of the joints and connections to avoid damage to the overall construction. Furthermore, the board moisture directly before application of the render must be < 13 % by mass, measured e.g. with measurement device Gann Hydromette BL H 41.

The properties of the boards change with a high level of material moisture. During unfavourable weather conditions with poor evaporation performance, the exposure to outdoor weather is limited to 14 days.

By a surface-pressed application and the application of the entire reinforcement layer render thickness of at least 7 mm with mesh reinforcement, a maximum exposure to outdoor weather of 6 months is possible.

Before application of the top coat the substrate properties must be tested (suction properties, level of soiling). A suitable primer is necessary if required. Alternatively, a sheet which is open to diffusion can be used as a temporary weather protection foil. Formation of condensation must be avoided. Open areas must be protected against permanent exposure to weather during installation (e.g. window reveals / parapets).

Driving-rain proof window connection profile

Profile selection

Window connection profiles	Features	Total plaster thickness
Duo G10	With shadow gap, two-part profile	6 – 15 mm
Duo G6	With shadow gap, two-part profile	6 – 12 mm
Milano	With protective lip, two-part profile	6 – 10 mm
Universal Pro	With shadow gap and integrated PUR sealing tape	6 – 12 mm
Front mounted roller shutters	With shadow gap and membrane for roller blind guide rails	6 – 10 mm

Application

Window connection profiles	Movement absorption capacity	Window position in wooden stud																																																																										
		Centred			Flush			Projected (plasterable reveal necessary)																																																																				
Maximum insulation material thickness in mm with window size																																																																												
<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 10%;"></th> <th style="width: 10%;"></th> <th style="width: 10%;">$\leq 6 \text{ m}^2$</th> <th style="width: 10%;">$\leq 10 \text{ m}^2$</th> <th style="width: 10%;">$\leq 15 \text{ m}^2$</th> <th style="width: 10%;">$\leq 6 \text{ m}^2$</th> <th style="width: 10%;">$\leq 10 \text{ m}^2$</th> <th style="width: 10%;">$\leq 15 \text{ m}^2$</th> <th style="width: 10%;">$\leq 6 \text{ m}^2$</th> <th style="width: 10%;">$\leq 10 \text{ m}^2$</th> <th style="width: 10%;">$\leq 15 \text{ m}^2$</th> </tr> </thead> <tbody> <tr> <td>Duo G10</td> <td>A</td> <td>80</td> <td>80</td> <td>–</td> <td>80</td> <td>80</td> <td>–</td> <td>80</td> <td>80</td> <td>–</td> </tr> <tr> <td>Duo G6</td> <td>B</td> <td>80</td> <td>80</td> <td>–</td> <td>80</td> <td>80</td> <td>–</td> <td>80</td> <td>80</td> <td>–</td> </tr> <tr> <td>Milano</td> <td>A</td> <td>80</td> <td>80</td> <td>–</td> <td>80</td> <td>80</td> <td>–</td> <td>80</td> <td>80</td> <td>–</td> </tr> <tr> <td>Universal Pro</td> <td>A</td> <td>80</td> <td>80</td> <td>80</td> <td>80</td> <td>80</td> <td>80</td> <td>80</td> <td>80</td> <td>80</td> </tr> <tr> <td>Front mounted roller shutters</td> <td>A</td> <td>80</td> <td>80</td> <td>–</td> <td>80</td> <td>80</td> <td>–</td> <td>80</td> <td>80</td> <td>–</td> </tr> </tbody> </table>													$\leq 6 \text{ m}^2$	$\leq 10 \text{ m}^2$	$\leq 15 \text{ m}^2$	$\leq 6 \text{ m}^2$	$\leq 10 \text{ m}^2$	$\leq 15 \text{ m}^2$	$\leq 6 \text{ m}^2$	$\leq 10 \text{ m}^2$	$\leq 15 \text{ m}^2$	Duo G10	A	80	80	–	80	80	–	80	80	–	Duo G6	B	80	80	–	80	80	–	80	80	–	Milano	A	80	80	–	80	80	–	80	80	–	Universal Pro	A	80	80	80	80	80	80	80	80	80	Front mounted roller shutters	A	80	80	–	80	80	–	80	80	–
		$\leq 6 \text{ m}^2$	$\leq 10 \text{ m}^2$	$\leq 15 \text{ m}^2$	$\leq 6 \text{ m}^2$	$\leq 10 \text{ m}^2$	$\leq 15 \text{ m}^2$	$\leq 6 \text{ m}^2$	$\leq 10 \text{ m}^2$	$\leq 15 \text{ m}^2$																																																																		
Duo G10	A	80	80	–	80	80	–	80	80	–																																																																		
Duo G6	B	80	80	–	80	80	–	80	80	–																																																																		
Milano	A	80	80	–	80	80	–	80	80	–																																																																		
Universal Pro	A	80	80	80	80	80	80	80	80	80																																																																		
Front mounted roller shutters	A	80	80	–	80	80	–	80	80	–																																																																		
Duo G10	A	80	80	–	80	80	–	80	80	–																																																																		
Duo G6	B	80	80	–	80	80	–	80	80	–																																																																		
Milano	A	80	80	–	80	80	–	80	80	–																																																																		
Universal Pro	A	80	80	80	80	80	80	80	80	80																																																																		
Front mounted roller shutters	A	80	80	–	80	80	–	80	80	–																																																																		



Notes	Always apply window connection profiles in timber construction with additional joint sealing tape FD.
	Back profile joints with Fugendichtband FD joint sealing tape. Backing for Universal Pro is not necessary (observe the product data sheet).
	When using window connection profiles, the VDPM leaflet "Formation of details with profiles and joint sealing tapes in external rendering and ETICS" (German only) and the current window guideline of the Fachverband der Stuckateure "Connections windows and roller shutters in rendering, external thermal insulation composite system and drywalling" (German only) must be observed.
	For coloured metal and plastic windows, the use of profiles with high shear resistance (higher movement class, e.g. instead of class B → class A) is recommended.

Use of adhesively bonded window connection profiles

An adhesive bonding test must be performed before the use of adhesively bonded window connection profiles. For this purpose, clean a concealed location with a clean and dry cloth (without cleaning agent). The substrate should be level, dry and dust free. Residues that can affect bonding must be removed. The temperature must be between +5 °C and +40 °C. Cut off a short section of the profile (approx. 100 mm), peel off the protective paper of the PE-Dichtband sealing tape and push the profile section firmly on. Wait 10 minutes and then tear the profile with force away from the substrate. The substrate is suitable if the self-adhesive PE-Dichtband sealing tape on the one hand remains completely attached to the profile and on the other hand completely to the substrate (continuous foam rupture). Should this not be the case, the window connection profile Universal Pro with PUR sealing tape must be used.


Driving-rain proof window connection profiles (continued)

Window connection with roller blind guide rails



Scheme drawings

Connection to window sill side section




Example: Application in conjunction with a second water channelling level


Dimensions in mm

Applied render system

Mineral based



Mineral / organic



Reinforcement (basecoat) layer

Façade reinforcement

System	Basecoat ¹⁾	Layer thickness	Reinforcement mesh	Mesh arrangement in the reinforcement layer	Mesh reinforcement joint overlap
Mineral based	Luis	7 mm	See following table ²⁾	In the upper third	≥ 100 mm
Mineral / organic	SM700 Pro	7 – 10 mm			

1) The reinforcement thickness is specified in the approval with 5 mm. We always recommend a reinforcement thickness of 7 mm on wood fibre insulation panels.

2) With Noblo 1.5 mm an additional mesh layer is recommended.

Reinforcement in dependence on the finishing plaster and luminosity of the finish coating

Render finish	Graining mm	Luminosity of the finish coat			
		Siliconharz-EG-Farbe, Autol, Minerol, MineralAktiv Fassadenfarbe paint 100 to 30	29 to 25	24 to 20	Autol TSR ³⁾ < 20
Noblo Filz, SM700 Pro	1.0	•	•	•	•
Noblo Filz	1.5	•	•	•	•
Noblo	1.5	••	••	••	••
	2.0 – 3.0	•	•	•	•
RP 240, SP 260 Pro	2.0 – 5.0	•	•	•	•
MineralAktiv Scheibenputz floated render	1.5 – 3.0	•	•	•	–
Conni S, Addi S	1.5 – 3.0	•	•	•	•

3) Functionality only on white, newly created finish coats is guaranteed in combination with an at least 5 mm thick, mineral reinforcement layer.

- Single-layer mesh reinforcement
- Double-layer mesh reinforcement

Reinforcement layer (continued)

The insulation panels must have a moisture level of < 13 % by mass when the render is applied. Consider changes in material moisture due to air humidity.

Initially apply basecoat as a surface-pressed layer on the board surface. Then the basecoat layer is subsequently built up as wet plaster on wet plaster.


At the inside corners of openings (e.g. window reveal - lintel), embed reinforcement mesh strips or mesh corner angle reinforcement fully into the basecoat. Subsequently apply Gewebeeckwinkel mesh corner angles perpendicular and flush. Apply the reinforcement layer and level it. Except when using Gewebeeckwinkel Sturzecke mesh corner angle for lintel corner, extending diagonally from all opening corners embed Gewebeeckpfeile mesh corner arrows or approx. 300 x 500 mm strips of reinforcement mesh in the fresh mortar. Subsequently embed Armiergewebe reinforcement mesh on the entire surface with at least a joint overlap of 100 mm fresh-in-fresh in the upper third of the basecoat layer. Apply a full covering of basecoat to the mesh.

If a double layer of reinforcement is required (see Page 41), an approx. 4 mm thick basecoat layer is applied to the existing surface-pressed layer in which the reinforcement mesh is applied crease-free and with a joint overlap of approx. 100 mm in the upper third. After the basecoat layer has hardened, the second basecoat mesh is embedded with a joint overlap of ≥ 100 mm to the first mesh and a joint overlap to one another of ≥ 100 mm in the second layer of the basecoat. The position of the second mesh corresponds to the position of a simple reinforcement with a mesh. Alternatively, the second reinforcement layer can also be applied onto the fresh first reinforcement layer. For this purpose, apply minimum 3 mm of basecoat as wet plaster on wet plaster onto the first basecoat layer and apply reinforcement mesh with staggered joints. The diagonal reinforcements are embedded before the second mesh layer.

Avoid excessive smoothing of the reinforcement layer to prevent a concentration of fine particles or formation of a sinter layer on the surface. Rub off any burrs that have formed when drying. Should natural discolourations occur on the reinforcement (basecoat) layer, apply Aton Sperrgrund barrier coating as a plaster primer when dry. Plaster connections should be separated from the constructional components with a separating strip (e.g. SR band), separation cut, profiles or similar.


Reinforcement of window lintel/reveal

Image 1



The lintel/reveal corner areas require additional Gewebeeckwinkel Sturzecke mesh corner angle reinforcement.

Image 2



Alternatively, the lintel/reveal corner areas can be reinforced with Gewebeeckpfeile mesh corner arrow or reinforcement mesh strips.

Basecoat drying time

Before application of a further coating (primer/basecoat) it is important to ensure that the basecoat is fully dry. The minimum drying time is generally approx. 1 day/mm layer thickness. With unfavourable weather conditions (e.g. high levels of air humidity or low temperatures), the drying time is extended, e.g. the drying time at +5 °C is around double so long. For further information please refer to the product data sheets of the subsequent coatings.


Plinth and splash water zone

Apply preferably at least 5 mm basecoat covering the full surface and embed reinforcement mesh 4x4 mm or 5x5 mm to the entire surface in the upper third of the basecoat. Stagger the joints by at least 100 mm.

When insulation is applied in areas contacting the soil, the reinforcement layer ends underneath the edge of the future ground line.

Reinforcement layer (continued)

Thermal bridge free Peri plinth end profile



Apply the basecoat on the insulation material. Push in the Peri plinth connection profile between the perimeter / plinth insulation and façade insulation or Peri mounting rail and façade insulation, push into the basecoat, align flush and embed the reinforcement mesh.

Connect the profiles with the supplied connectors. Provide the outside corners with the appropriate mitring or suitable corner elements. Constructional separation of the plinth plaster, e.g. by using a separating strip (SR tape), separation cut, profile or similar. When implementing the transition between the façade insulation and the plinth insulation, driving-rain proofing must be observed. If necessary apply a Fugendichtband FD joint sealing tape.

Finish coat

Primers

Stir the contents of the container thoroughly and repeat occasionally.

With thin-layer mineral-based finishing coats, when required use undiluted Quarzgrund Pro, or Isogrund, diluted 1:1 with clean water and apply uniformly with a roller to the entire surface or apply using a suitable spray device. With Conni and Addi: Apply undiluted Quarzgrund Pro uniformly using a roller or brush and spread crosswise. Avoid streaking. When applying pigmented Conni and Addi, Quarzgrund Pro pigmented in the same or similar colour shade is recommended.

Allow a drying time of at least 2 hours before applying the finishing coat with Quarzgrund Pro and at least 12 hours for Isogrund.

Plaster application

Required water quantity and mixing of the mortar in acc. with the current product data sheet.

Check the containers before use to ensure that the colour shades are correct. When applying a shaded finish coat, ensure that the batch numbers are the same or only mix sufficient render required to finish a full rendered surface. Slight differences in colour hues can occur due to the use of natural aggregates. When reordering, always state the consignment number of the previous delivery.

Ensure uniform grain distribution.

The type of tool used influences the surface roughness and it is therefore essential to use the same tool for a consistent finish. Ensure that there are sufficient workers available on every scaffolding level to avoid bothersome structural effects. Work quickly fresh in fresh and do not rework hardened surfaces. Avoid interruptions when working on continuous surfaces and always complete the work on self-contained surfaces.

Observe Code of Practice no. 26 "Farbveränderungen von Beschichtungen im Außenbereich - Colour changes in exterior coatings" of the Bundesausschuss Farbe und Sachwertschutz (Federal Paint and Property Protection Committee).

Plaster connections should be separated from the constructional components with a separating strip (e.g. SR tape), separation cut, profiles or similar.

Finishing plaster	Layer thickness in mm
Façade	
Noblo Filz (freely styled texture)	3 – 5
Noblo Filz	2 – 3
Noblo, SP 260 Pro, RP 240	Grain size
SM700 Pro (sponged / freely styled texture)	3
Conni S, Addi S	Grain size
MineralAktiv Scheibenputz floated render	Grain size
Plinth area	
Sockel-SM Pro (sponged) ¹⁾	2
Sockel-SM (sponged) ²⁾	2
Butz	2

1) Only in conjunction with Sockel-SM Pro as a basecoat. Sockel-Dicht is unnecessary in case Sockel-SM Pro is used as a render system (basecoat and finish coat) in a total thickness ≥ 7 mm.

2) Only in conjunction with Sockel-SM as a basecoat.

Finish coat (continued)

Plaster application (continued)

Noblo Filz

Apply a fully covering coat of Noblo Filz in grain thickness, allow to stiffen and then apply a second coat in grain thickness, and immediately sponge / felt, without using water. Apply approx. 3 to 5 mm for free textures, spread flush and texture immediately with the required tool.

Noblo, SP 260 Pro, RP 240

Apply the render with a stainless steel finishing trowel or trowel, spread flush in grain size and structure immediately as required using a suitable tool.

SM700 Pro

For sponged surfaces SM700 Pro is applied in a layer thickness of approx. 3 mm on the basecoat and sponged after initial setting or freely textured.

MineralAktiv Scheibenputz floated render

Knauf MineralAktiv Scheibenputz floated render is applied over the entire surface in grain thickness with a stainless steel trowel, and directly after application it is worked uniformly and without interruption to the desired texture using a hard plastic trowel. A sponge rubber float produces a coarser more rustic texture finish.

Conni S, Addi S

Ready-to-use, paste-like finish coat must be mixed thoroughly. When necessary, a small quantity of water may be added to set the application consistency. Apply Conni S or Addi S (floated render texture) with a stainless steel trowel in grain size to the entire surface and trowel smooth with circular movements without interruption using a hard plastic trowel.

Plinth and splash water zone

Apply a primer to suit the selected top coat, observe the required drying times. Apply plinth renders, e.g. Sockel-SM Pro or Sockel-SM on the following day on the system-compatible reinforcement layer and sponge.

Sockel-SM

The layer thickness as a basecoat should be at least 5 to 7 mm. Apply Sockel-SM for sponged surfaces (layer thickness 1 to 2 mm) one day later at the earliest to the basecoat layer already applied with Sockel-SM. Sponge Sockel-SM as the mortar dries.

Sockel-SM Pro

When applying with Sockel-SM Pro render system in a total layer thickness (basecoat and finish coat) of at least 7 mm, additional moisture protection with Sockel-Dicht is unnecessary.

Butz

Allow a drying time of at least 2 hours before applying Butz on Quarzgrund Pro. Mix the contents of the container well, apply using a stainless steel trowel slightly thicker than the grain size and level in one direction.

Plaster seal / moisture protection

A plaster system (with exception of: Sockel-SM Pro) must be protected against the ingress of moisture in damp and water hazard areas. This also applies for balconies, loggias, flat roofs and terraces.

The required plaster sealing or the necessary moisture protection must be applied up to at least 50 mm above the edge of the ground line or top edge of the covering. In case of stairs, the plaster sealing should be applied at least 80 mm above the step, as it is necessary to assume an increased exposure to moisture here. In our case, this must be applied up to the existing building sealing.

In case of plastered insulation panels that are connected to the existing on-site perimeter insulation, it is necessary to ensure that the lower plaster edge is protected against the ingress of moisture by the plaster seal / moisture protection.

As plaster seal / moisture protection, Sockel-Dicht must be applied in a dry layer thickness of at least 1 mm (wet layer thickness at least 1.2 mm) in two work steps, e.g. with a trowel or wide (water) brush. In case of a paintable consistence, Sockel-Dicht is applied with a prime brush, in case of a plasterable consistence it is applied with a spatula, finishing trowel or trowel. The application is performed in two stages.

Mechanical protection in the plinth area

As protection for the plinth in the area contacting the soil against mechanical influences of the soil or gravel bed, use of on-site protective layer with slip membrane (e.g. fleece laminated dimpled sheet) up to the edge of the ground line is recommended.

Paint coats

Primers

A suitable primer for a façade paint can be found in the product data sheets for the façade paints.

Casiol Grund is a ready-to-use, white pigmented, highly permeable, mineral calcium silicate primer for reducing the risk of lime efflorescence, as well as for equalising the suction properties on alkaline finishing renders before applying paint coats (medium to intensive colour shades).

Façade paint

Mineral finishing coats (without MineralAktiv Scheibenputz floated render) are generally provided with an equalization coat of Siliconharz-EG-Farbe paint.

Use a trial coat to ensure the colour shade is correct. Never apply the content from different buckets together on a common wall. Mix the contents together in a clean bucket beforehand. Stir the contents of the bucket thoroughly. The application consistence can be modified in acc. with the product data sheet. Apply a thin and even paint coat crosswise without joints on the fully hardened and dried finish coat. Always complete surfaces that can be viewed together on the same day.

Notes

All the products listed here are formulated, so that a preventative and retarding action against soiling is in effect. Permanent protection against soiling caused by microorganisms such as algae and fungus cannot be guaranteed. The susceptibility depends on the local and environmental conditions. Loss of the technical function of the finish coat and/or the paint coat due to fouling of the surface with mould and mildew is practically excluded.

Refer to "Guideline on inspection obligations upon delivery of ceramic / pottery goods within the scope of the duty to inspect and give notice of defects (§ 377 HGB)" (German only), also refer to vdpm.info/services/downloads.

Observe the Code of Practice "Egalisationsanstriche auf Edelputzen – Farbtonegalisierende Beschichtung - Equalization coats on finishing plasters", see also vdpm.info/services/downloads.

Maintenance

Maintenance of the façade surface should be performed at regular intervals taking the size, architecture and location into consideration.

Maintenance is understood to mean cleaning, painting or, if required, renewing of connections (maintenance joints) on the intact External Thermal Insulation Composite Systems (ETICS). It is necessary to undertake corrective measures as quickly as possible if a maintenance issue is identified in order to assure the ETICS service life and protect the visual appearance. We generally recommend consulting experienced and qualified specialist companies if a maintenance issue is identified.

Plaster surfaces

Perform an inspection of the plaster surfaces on the basis of the standard DIN 18550-1. In every case, the driving-rain proof protection of the exterior wall and the permanent weather resistance of the overall system must be assured.

Inspect for	Technical instructions and measures
Soiling	Clean using a high-pressure water jet (water temperature below +60 °C, observe the regional wastewater discharge regulations) and if required, apply a new coat of paint to the façade with a system-conform paint once sufficiently dry.
Microbiological growth (e.g. algae, mould)	Clean using a high-pressure water jet (water temperature below +60 °C, observe the regional wastewater discharge regulations), apply Algizid (ready-to-use remediation solution) and if required, apply a new coat of paint to the façade with a system-conform paint once sufficiently dry.
Sealing of elastic connections (windows, doors, expansion joints, façade penetrations)	Joints applied with permanently-elastic materials are maintenance joints and should be inspected and replaced at regular intervals, if required, or sealed to repel moisture.
Mechanical damage	Fill with equivalent insulation materials, reapply the render including the reinforcement mesh, and if necessary, apply a new coat of paint with a system-conform paint. Repairs to small areas and spots may stand out visually from the rest of the surface. Differences in texture and colour of the finishing coat may be visible.

Material requirement without allowance for loss and waste

Plinth	Façade	System components	Remark	Unit	Quantity as average value	
					WE203Ta.de Mineral based	WE203Tc.de Mineral / organic
Bonding layer per m ² plinth, e.g. on bituminous waterproof sealing						
● ¹⁾		Socket-Dicht	Layer thickness 2 mm	kg	3.8	
Adhesive per m ² plinth insulation (40 %–100 % adhesive area ratio)						
●		SM700 Pro	Max. layer thickness 5 mm	kg	2.9 – 7.1	
●		Luis		kg	2.2 – 3.5	
●		Socket-SM		kg	4.0 – 8.0	
● ²⁾		Socket-SM Pro		kg	4.0 – 8.0	
Insulation material per m ²						
●		Plinth insulation panel	Insulation material thickness: Up to 80 mm → Integration into the soil: Up to 3 m	m ²	1	
●		AGEPAN® THD Putz 050	Thickness 40 – 80 mm	m ²	1	
Plinth connection per m Only with recessed plinth						
●		Plinth connection profile	Projection of 30 to 80 mm	m/m	1	
●		Plinth profile	Plinth profile with drip edge and reinforcement mesh for layer thickness 10 mm or 14 mm	m/m	1	
●		Assembly kit plinth end profiles	Fasteners	Set/m	0.04	
●		Peri plinth end profile	For layer thickness 7 or 17 mm	m/m	1	
●		Peri installation rail	Plastic profile for supporting Peri plinth connection profile, projection of 50 to 80 mm	m/m	1	
Fasteners per m ² façade insulation material ³⁾						
●		CNplus 8 insulation anchor nail	Anchoring depth s ≥ 35 mm, ≥ 55 mm for category D and E	pcs.	2 dowels per plinth insulation panel from a height of 150 mm above the edge of the ground line on solid substrates	
●		Schraubdübel STR U 2G dowel	Anchoring depth s ≥ 25 mm, ≥ 65 mm for category E		Number of fasteners dependent on the wind load, see tables Page 15 and 16	
● ⁴⁾	●	Schraubdübel STR H dowel	Anchoring depth s ≥ 30 mm			
● ⁴⁾	●	Schraubdübel 6H dowel	Anchoring depth s ≥ 30 mm			
● ⁴⁾	●	Broadback staples ⁵⁾	Anchoring depth s ≥ 30 mm			
Basecoat per m ²						
●	●	SM700 Pro	Layer thickness 7 – 10 mm	kg	10.0 – 13.0	10.0 – 13.0
●	●	Luis	Layer thickness 7 mm	kg	10.0	10.0
●		Socket-SM	Layer thickness 5 – 7 mm	kg	7.0 – 10.0	7.0 – 10.0
● ⁶⁾		Socket-SM Pro	Layer thickness 5 mm	kg	8.0	8.0
Reinforcement mesh per m ²						
●	●	Reinforcement mesh 4x4 mm	100 mm joint overlap	m ²	1.1	1.1
●	●	Reinforcement mesh 5x5 mm	100 mm joint overlap	m ²	1.1	1.1
Primer per m ²						
●	●	Isogrund (recommended)	Diluted: 1:1 with water	kg	(0.1)	–
●	●	Quarzgrund Pro ⁷⁾	Undiluted	kg	0.17	0.17

1) When bonding on bituminous waterproofing apply Socket-Dicht as a bonding layer, in case Socket-SM Pro is not used.

2) Socket-Dicht as a bonding layer is not required when using Socket-SM Pro as an adhesive on bituminous sealants.

3) Plinth insulation panels that are adhesively bonded to the building waterproofing must be anchored with 2 dowels/panel from a height of 150 mm above the top edge of the ground line.

4) For the plinth area with wooden substructure and plinth insulation panel.

5) Steel staples acc. to EN 14592, $b_r \geq 27.5$ mm, $t_n \geq 2.0$ mm, $l_n \geq 75$ mm, anchoring depth at least 30 mm, made of stainless steel.

6) In conjunction with Socket-SM Pro as a finish coat. With total layer thickness ≥ 7 mm moisture protection with Socket-Dicht is unnecessary.

7) With a coloured finishing top coat Quarzgrund Pro in the same colour shade is recommended.

Material requirement without allowance for loss and waste (continuation)

Plinth	Façade	System components		Remark	Unit	Quantity as average value	
						WE203Ta.de Mineral based	WE203Tc.de Mineral / organic
Finish coat per m²							
•	•	SM700 Pro sponged / freely styled texture	Grain size 1.0 mm	Layer thickness 3 mm	kg	4.2	–
•	•	SM 260 Pro	2.0 mm	Layer thickness 2 mm	kg	3.2	–
			3.0 mm	Layer thickness 3 mm	kg	3.4	–
			5.0 mm	Layer thickness 5 mm	kg	5.0	–
•	•	RP 240	2.0 mm	Layer thickness 2 mm	kg	3.1	–
			3.0 mm	Layer thickness 3 mm	kg	3.8	–
			5.0 mm	Layer thickness 5 mm	kg	5.0	–
•	•	Noblo	1.5 mm ¹⁾	Layer thickness 1.5 mm	kg	2.3	–
			2.0 mm	Layer thickness 2 mm	kg	2.8	–
			3.0 mm	Layer thickness 3 mm	kg	3.4	–
•	•	Noblo Filz	1.0 mm	Layer thickness 2 mm	kg	3.2	–
			1.5 mm	Layer thickness 3 mm	kg	4.6	–
•	•	MineralAktiv Scheibenputz floated render	1.5 mm	Layer thickness 1.5 mm	kg	2.4	–
			2.0 mm	Layer thickness 2 mm	kg	3.2	–
			3.0 mm	Layer thickness 3 mm	kg	4.2	–
•	•	Conni S	1.5 mm	Layer thickness 1.5 mm	kg	–	2.2
			2.0 mm	Layer thickness 2 mm	kg	–	2.8
			3.0 mm	Layer thickness 3 mm	kg	–	3.7
•	•	Addi S	1.5 mm	Layer thickness 1.5 mm	kg	–	2.2
			2.0 mm	Layer thickness 2 mm	kg	–	2.8
			3.0 mm	Layer thickness 3 mm	kg	–	3.7
• ²⁾		Sockel SM Pro (sponged)	1.0 mm	Layer thickness 2 mm	kg	3.0	–
• ³⁾		Sockel SM (sponged)	1.0 mm	Layer thickness 2 mm	kg	3.0	–
•		Butz	2.0 mm	Layer thickness 2 mm	kg	–	4.5
Plaster seal / moisture protection per m²							
•		Sockel-Dicht		Layer thickness min. 1 mm (two coats)	kg	1.8	1.8
Primer per m²							
•	•	Casiol Grund		Undiluted	l	0.17	–
Coat per m²							
•	•	Siliconharz-EG-Farbe paint		Single coat ⁴⁾	l	0.17 – 0.22 ⁵⁾	0.17 – 0.22 ⁵⁾
•	•	Autol		Double coat	l	0.25 – 0.40 ⁶⁾	0.25 – 0.40 ⁷⁾
•	•	Autol TSR ⁸⁾		Double coat	l	0.25 – 0.40 ⁶⁾	0.25 – 0.40 ⁷⁾
•	•	Minerol		Double coat	l	0.25 – 0.40 ⁶⁾	–
•	•	MineralAktiv Fassadenfarbe paint		Double coat	l	0.28 – 0.40 ⁶⁾	0.28 – 0.40 ⁷⁾

1) Additional mesh layer in basecoat is recommended.

2) Only in conjunction with Sockel-SM Pro as a basecoat and with a total layer thickness ≥ 7 mm Sockel-Dicht is not required.

3) Only in conjunction with Sockel-SM as a basecoat.

4) Recommendation: Double coat for enhanced weather-proofing (see "Code of Practice No. 9 - Coatings on mineral renders" from the German Bundesausschuss Farbe und Sachwertschutz).

5) Not required on MineralAktiv Scheibenputz floated render or Conni S.

6) Only permissible on MineralAktiv Scheibenputz floated render.

7) Only permissible on Conni S.

8) Functionality only on at least 5 mm thick mineral reinforcement layer and only on white, newly created finish coats possible.

Information on the sustainability of Knauf WARM WALL Natur T in Timber Construction

Building assessment systems ensure the sustainable quality of buildings and constructional structures by a detailed assessment of ecological, economic, social, functional and technical aspects.

In Germany, the following certification systems are of particular relevance:

- DGNB System
Deutsches Gütesiegel Nachhaltiges Bauen
- BNB
Bewertungssystem Nachhaltiges Bauen - Quality rating system for environmentally sustainable building)
- LEED
Leadership in Energy and Environmental Design

Knauf WARM WALL systems can positively influence many of these criteria.

DGNB/BNB

Ecological quality

- Total primary energy requirement
Reduction of the building energy requirement over the entire lifecycle due to efficient WARM WALL systems
- Use of sustainable resources / wood:
The wood of the wood fibre façade boards originates from sustainable forestry, FSC certified and PEFC certified

Economic quality

- Building related life-cycle costs:
Reduction of the operating costs due to cost-effective WARM WALL systems

Sociocultural and functional quality

- Thermal comfort in summer or winter:
Cozy room climate with WARM WALL systems

Technical quality

- Premium quality thermal and moisture protection for the building shell:
With WARM WALL systems significantly exceeding GEG requirements

LEED

Materials and Resources

- Regional Materials:
Regional material availability depending on location of building.
Information on request
- Certified Wood;
The wood of the wood fibre façade boards originate from sustainable forestry, FSC certified and PEFC certified



Videos for Knauf systems and products can be found under the following link:

youtube.com/knauf



Find the right system for your requirements!

knauf.de/systemfinder



The Knauf Infothek App now provides all the current information and documents from Knauf Gips KG at any time and in every location in a clear and comfortable way.

knauf.de/infothek

Knauf Direct

Technical Advisory Service:

▶ knauf-direkt@knauf.com

▶ www.knauf.de

Knauf Gips KG Am Bahnhof 7, 97346 Iphofen, Germany

All technical changes reserved. Only the current printed instructions are valid. The stated information represents current state-of-the-art Knauf technology. The entire state of approved engineering rules, appropriate standards, guidelines, and rules of craftsmanship are not included herewith. These and all application instructions have to be adhered to separately by the installer. Our warranty is expressly limited to our products in flawless condition. All application quantities and delivery amounts are based on empirical data that are not easily transferable to other deviating areas.

All rights reserved. All amendments, reprints and photocopies, including those of excerpts, require our expressed permission.